

DATE: Thursday, October 5, 2006			TABULATION OF BIDS				GENERAL ENGINEERING CO.				
TIME: 2:00 PM, CDT			Camp Chi Dam Repairs				P.O. Box 340, 916 Silver Lake Drive				
PLACE: General Engineering Company			Jewish Community Centers of Chicago				Portage, WI 53901				
CONTRACTOR:			Terra Engineering 2201 Vondron Road Madison, WI 53718		Norcon Corporation 5600 Municipal Street Schofield, WI 54476		Engineering&Const. Innovations 780 Barge Channel Road St. Paul, MN 55107		Engineering&Const. Innovations 780 Barge Channel Road St. Paul, MN 55107		
Addendum No. 1:			X		X		X		X		
Bid Bond:			X		X		X		X		
Certified Check:									ALTERNATE BID		
Dam Repairs											
No.	Description	Qty.	Unit	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
1	Performance and Payment Bonds: Provide performance and payment bonds as specified.	1	LS	\$ 1,900.00	\$ 1,900.00	\$ 2,770.00	\$ 2,770.00	\$ 2,300.00	\$ 2,300.00	\$ 2,050.00	\$ 2,050.00
2	Tree and Brush Removal: Provide all labor, materials, and equipment necessary to remove trees and brush on both the left and right abutment areas on both the downstream and upstream sides of the dam and treat with herbicide.	1	LS	\$ 8,000.00	\$ 8,000.00	\$ 5,306.00	\$ 5,306.00	\$ 2,750.00	\$ 2,750.00	\$ 2,750.00	\$ 2,750.00
3	Underwater Inspection: Provide all labor, materials, and equipment necessary to provide an underwater inspection of the existing slide gate to determine the exact size and mounting configuration, the end conditions of the drawdown pipes, and the condition of the upstream dam face.	1	LS	\$ 3,900.00	\$ 3,900.00	\$ 4,652.00	\$ 4,652.00	\$ 5,900.00	\$ 5,900.00	\$ 5,900.00	\$ 5,900.00
4	Coffer Dam: Provide all labor, materials, and equipment necessary to install and remove a coffer dam to allow replacement of the slide gate.	1	LS	\$ 22,900.00	\$ 22,900.00	\$ 32,658.00	\$ 32,658.00	\$ 62,000.00	\$ 62,000.00	No Bid	\$ -
5	Slide Gate: Provide all labor, materials, and equipment necessary to furnish and install the slide gate including gate, floor stand and crank, plug valve, plug valve accuator extension, and removing soil and debris from spillway.	1	LS	\$ 28,500.00	\$ 28,500.00	\$ 38,457.00	\$ 38,457.00	\$ 20,500.00	\$ 20,500.00	\$ 62,500.00	\$ 62,500.00

DATE: Thursday, October 5, 2006		TABULATION OF BIDS				GENERAL ENGINEERING CO.					
TIME: 2:00 PM, CDT		Camp Chi Dam Repairs				P.O. Box 340, 916 Silver Lake Drive					
PLACE: General Engineering Company		Jewish Community Centers of Chicago				Portage, WI 53901					
CONTRACTOR:		Terra Engineering 2201 Vondron Road Madison, WI 53718		Norcon Corporation 5600 Municipal Street Schofield, WI 54476		Engineering&Const. Innovations 780 Barge Channel Road St. Paul, MN 55107		Engineering&Const. Innovations 780 Barge Channel Road St. Paul, MN 55107			
Addendum No. 1:		X		X		X		X			
Bid Bond:		X		X		X		X			
Certified Check:								ALTERNATE BID			
6	Abandon Pipes: Provide all labor, materials, and equipment necessary to remove the gate valves from the two drawdown pipes and provide blind flanges.	1	LS	\$ 11,000.00	\$ 11,000.00	\$ 4,327.00	\$ 4,327.00	\$ 13,500.00	\$ 13,500.00	\$ 13,500.00	\$ 13,500.00
7	Concrete Repair: Provide all labor, materials, and equipment necessary to repair the concrete on the downstream face of the dam using polymer-modified concrete and stainless steel anchors.	300	SF	\$ 189.00	\$ 56,700.00	\$ 253.00	\$ 75,900.00	\$ 234.75	\$ 70,425.00	\$ 234.75	\$ 70,425.00
8	Pipe Insulation: Provide all labor, materials, and equipment necessary to replace the existing insulation including removal and disposal of insulation, furnishing and installation of insulation and covering, and replacement of pipe hangers.	1	LS	\$ 18,000.00	\$ 18,000.00	\$ 17,142.00	\$ 17,142.00	\$ 13,825.00	\$ 13,825.00	\$ 13,825.00	\$ 13,825.00
TOTAL CONTRACT 1:				\$ 150,900.00		\$ 181,212.00		\$ 191,200.00		\$ 170,950.00	
REMARKS:		1		3		4		2			

* ALTERNATE BID